

Bid Addendum Report

Melauli Municipality

Melauli Municipality
Melauli Municipality, Melauli, Baitadi, Nepal
Baitadi
Sudoor Pachism Province
Nepal

Addendum No: 2

Published On: 31-12-2020 00:00

Invitation No: 10/RC/2077/078

Dated On: 29-12-2020 00:00




Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	2020-12-29 14:00:00	2020-12-31 00:00:00
2	Bid Security Account Number	1490000037101	1490000013701

प्रमुख प्रशासकीय अधिकृत



Chapter: Bill of Quantities

1 Provisional Sum

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Relocation of services, minor infrastructures, irrigation canals, existing electric poles, Compensation etc. as per Engineer's instruction.	PS	1	200000	200000
2	insurance of work workmen and contractor equipment third party insurance including personal injury or death as per condition of contract and contract data	job	1	100000	100000
3	Provide and install Project Signboards. (Size 1.5mx1.2m)	Nos.	1	14283	14283

2 Construction work

2.1 Road Construction Work

2.1.1 Structure Works

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Clearing of grass, removing roots, breaking sods, levelling the surface and disposal as per specification.(SS/SP-201)	sq.m	2920.0			
2	Road way excavation in All type of Rocks and soils for fresh cutting, road width, curve/grade improvement etc. all complete as per specification. [900]	cu.m	4235.7			
3	Excavation for foundation through all types of soil including relevant lift and disposal upto 20m (a) Depth upto 1.5 m[907]	Cu.m	82.95			
4	Backfilling in layers in foundation pits,trenches with common excavated material etc including compaction and watering etc complete for depth of foundation upto 1.5m . [908]	Cu.m	18.71			
5	Providing and placing machine mixed M15/20 cement concrete for the foundation and footing etc. including compaction, curing, testing etc. all complete as per specification and drawing. [2000]	Cu.m	1.88			
6	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] including scaffolding, curing, preparation of mortar etc. complete, masoned height 0-5m, lead 30m (manual mixing), mortar 35% [2607]	Cu.m	17.85			
7	110 mm dia HDPE pipe for weep hole	rm	10.0			

प्रमुख प्रशासकीय अधिकृत



Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
8	Gabin Work Fabrication of hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diaphragms, with binding wire 12 swg, mesh wire 10 swg and selvedged wire 8 swg , including rolling, cutting and weaving ; assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, bedding, bonding and all transporation as per specification.	cu.m	26.5			
9	Providing, laying and fixing of Geo-textile (filter fabrics), lead 30m	sq.m	20.0			

भारुवा
Sudur Pashchim Province
Nepal

प्रमुख प्रशासकीय अधिकृत

Advertisement No. 2
Published On: 31-12-2070 BS-27
Information No: 16/REGISTRATION
Dated On: 14-12-7020 BS-20